

Friday 9/20

- The new road work began the week of September 17th through September 21st. We cannot complete the required work if cars are parked along the affected streets during the work day. Through traffic should stay away from these streets and consider other options. **Residents should use their driveway and inform their visitors or contractors they cannot park along the impacted streets during the workday for extended periods.**
- The grinding work was completed on Tuesday on all five streets.
- On Wednesday we patched various areas of the roads that have deteriorated badly and the storm sewer trenches on the five streets.
- Tonight we will post “Fresh Prime” signs to warn residents the priming operation will occur overnight. On Friday morning early, 4:00am, we will be priming the roads in preparation of placing the first lift of new asphalt on Friday. The streets need to be clear of all cars for the priming operation. The following streets will be impacted in the listed order:
 - Norfolk from Iroquois Avenue to Hiawatha Avenue
 - Oxford Avenue from Burlington Avenue north to Chicago Avenue
 - Tuttle Avenue from Burlington Avenue north to Chicago Avenue
 - Woodstock Avenue from Burlington Avenue north to Chicago Avenue
 - Arthur Avenue from Burlington Avenue north to Chicago Avenue
 - Norfolk Avenue from Ogden Avenue west to Iroquois Avenue
 - Norfolk Avenue from Hiawatha Avenue to the western Village limits
- **“Road closed”** signs will be posted to minimize the through traffic. These construction activities are moving operations traveling at speeds of 10 mph with lots of semi-trucks. Residents, school buses and emergency vehicles will still have access to the roads during the work day, but it is unlikely you will be able to drive by the active construction zone. Vehicles parked along the streets will be contacted by us to be moved and we ask for your understanding and cooperation.
- **Priming of these streets will occur on all five streets between 4:00 – 5:00am on Friday, September 21st so the prime can dry before traffic drives on it. PLEASE DRIVE SLOWLY ON THE PRIMED STREETS TO NOT GET IT ON YOUR CARS.**
- The first lift of new asphalt will be placed on Friday, September 21st. The roads should be fully open to normal traffic and activities at the end of the work day on Friday, September 21st.
- As they finish paving your street you will be able to drive on the new asphalt. It is the first lift and you cannot damage it.
- On Saturday, September 22nd, the crews will be back to finish any of the first lift of asphalt not completed tomorrow.
- On Monday September 24th they will adjust the manholes in the streets up to the finished road surface elevation. On Wednesday, September 26th and Thursday, September 27th we plan to install the final asphalt surface course on all five streets.
- Ditching, placement of topsoil and sod will resume after the asphalt surface course is complete. The new sod placement in the remaining parkways will probably take approximately 2 – 3 weeks to complete. The landscape contractor will continue to water the new sod numerous times, but any help the residents can provide is appreciated too. The contractors are responsible for the sod until it is established.

Your cooperation during construction is greatly appreciated. Typical construction work hours will be 7:00am to 5:00pm on Monday through Friday. We will notify the school districts and trash company of our schedule. We will coordinate as best as we can to get the trash picked up on Tuesdays. We need dry weather conditions for our schedule to be met. Rainy days will likely push the schedule back.

If you have any questions, please contact me at 224-315-0201 or you can call Clarendon Hills Public Works at 630-286-4750 between the hours of 7:00am to 3:30pm. After hours, please call 911 in the event of any emergencies.

Thank you for your cooperation and understanding.

Bill Sprague
On-Site Engineer